

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-24,523 00-01

LEASE NAME Schuster

WELL NUMBER 2

1650 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 1 TWP. 13 RGE. 20 (X) or (W)

COUNTY Ellis

Date Well Completed 9/7/88

Plugging Commenced 11/5/97

Plugging Completed 11/5/97

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR The Dane G. Hansen Trust

ADDRESS P. O. Box 187, Logan, Kansas 67646

PHONE#(785) 689-4816 OPERATORS LICENSE NO. 5285

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 5, 1997 (date)

by Rich Williams (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation LKC Depth to Top 3490 Bottom 3713 T.D. 3916

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	223'	None
				5 1/2"	3948'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
From Surface to 3850'. Pumped 32 sks Cement w/ 200# Hulls @ 200 PSI. Pumped 20 sks Gel w/300# Hulls @ 200 PSI. Pumped 82 sks Cement @ 200 PSI. Well pressured up to 1000 PSI. Close in 5 1/2" csg @ 250 PSI. Hooked up to 8 5/8" csg. No cement pumped. Pressured up 1000 PSI

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. _____

Address 1102 E. 8th Street, Hays, Ksnds 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: The Dane G. Hansen Trust

STATE OF KANSAS COUNTY OF PHILLIPS, ss.

Dane G. Bales

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dane G. Bales

(Address) P. O. Box 187, Logan, KS 67646

SUBSCRIBED AND SWORN TO before me this 10th day of November, 19 97



Betty Jane Bittel Notary Public

My Commission Expires: July 17, 2000.