

STATE OF KANSAS
STATE CORPORATION COMMISSION
290 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-051-21,480

LEASE NAME Rupp

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 22 TWP. 13S RGE. 19W ~~19W~~ (W)

COUNTY Ellis

Date Well Completed

Plugging Commenced 3-18-92

Plugging Completed 3-19-92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Braden-Deem, Inc.

ADDRESS 8100 E. 22nd N. #1800 Wichita, Ks. 67226

PHONE# (316) 685-6464 OPERATORS LICENSE NO. 5331

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed?, If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3780'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	233'	none
				4 1/2"	3773'	616'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Sanded bottom to 3400' dumped 4 sacks cement. Shot pipe @2600', 2300', 1800', 1200', 616'. 4 1/2" casing shot off @600', Mixed total of 300sacks cement w/500# hulls, 500# max pressure, Shut In 8 5/8" @100#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Braden-Deem, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *R. Darrell Kelso*

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 24 day of March, 19 92

Irma Herzberg
Notary Public

My Commission Expires:



15-057-21430-00-00

GREAT GUNS

R. A. Guard Log

FILE NO.	COMPANY ABERCROMBIE DRILLING, INC.			
	WELL RUPP NO. 1			
	FIELD			
	COUNTY ELLIS		STATE KANSAS	
	LOCATION: NE-SW-SE			OTHER SERVICES
	SEC 22 TWP 13S RGE 19W			
Permanent Datum	GROUND LEVEL		Elev. 2089	
Log Measured from	KELLY BUSHINGS 5 Ft. Above Permanent Datum			Elevations: KB 2094
Drilling Measured from	KELLY BUSHING			DF GL 2089
Date 5-22-78	GAMMA	NEUTRON	GUARD	CALIBER
Run No.	ONE	ONE	CNE	CNE
Depth—Driller	3780	3780	3780	3780
Depth—Logger	3779	3779	3779	3779
Bottom Logged Interval	3770	3778	3774	3767
Top Logged Interval	00	00	2900	2900
Casing — Driller	@	@	2 5/8 @ 240	@
Casing—Logger			240	
Bit Size			7 7/8	
Type Fluid in Hole			DRLG MUD	
Density and Viscosity			9.0 @ 38	
pH and Fluid Loss		cc	cc 10.5 @ 12	cc
Source of Sample			PIT	
Rm @ Meas. Temp.	@	°F	@ °F .6 @ 75	@ °F
Rmf @ Meas. Temp.	@	°F	@ °F .45 @ 75	@ °F
Rmc @ Meas. Temp.	@	°F	@ °F .9 @ 75	@ °F
Source of Rmf and Rmc			CHARTS	
Rm @ BHT	@	°F	@ °F .42 @ 107	@ °F
Time Since Circ.			2 HOURS	
Max. Rec. Temp. Deg. F		°F	°F 107	°F
Equip. No. and Location			28 HAYS	
Recorded By			R. GRANT	
Witnessed By			MR. CHENEY	

RECEIVED
STATE CORPORATION COMMISSION
FEB 17 1982
CONSERVATION DIVISION
WICHITA, KANSAS