

STATE OF KANSAS
STATE CORPORATION COMMISSION


15:051:00/51:00:00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

K111a

County. Sec. 20 Twp. 13 Rge. 19 (S) N (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW SW
Lease Owner **Mallonee Drilling Company, Inc.**
Lease Name **Dania** Well No. **1**
Office Address **812 Central Bldg., Wichita 2, Kansas**
Character of Well (completed as Oil, Gas or Dry Hole) **Dry hole**
Date well completed **October 12, 1956**
Application for plugging filed **October 12, 1956**
Application for plugging approved **October 12, 1956**
Plugging commenced **October 12, 1956**
Plugging completed **October 12, 1956**
Reason for abandonment of well or producing formation **nonproductive**

If a producing well is abandoned, date of last production 19...
Was permission obtained from the Conservation Division or its agents before plugging was commenced? **yes**

Name of Conservation Agent who supervised plugging of this well **Edson Petty**
Producing formation Depth to top Bottom Total Depth of Well **510** Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
		0	195	8 5/8	199'	CEMENTED

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from...feet to...feet for each plug set.

Mud thru Grill pipe to 196'. Mud plug set at 196'. 15 sacks mixed cement set at 196'. Drilling mud to 40'. Mud plug set at 40'. 10 sacks mixed cement to surface.

STATE CORPORATION COMMISSION
OCT 30 1956
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to **Mallonee Drilling Company, Inc.**
Address **812 Central Bldg., Wichita 2, Kansas**

STATE OF **Kansas**, COUNTY OF **Sedgwick**, ss.
.....(employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) **JW Mallonee**
812 Central Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this **16th** day of **October**, 19**56**

R.E. Mallonee
Notary Public.

My commission expires **March 7, 1957**

PLUGGING
FILE SEC 20 T 13 R 19W
BOOK PAGE 136 LINE 10

DRILLER'S LOG
#1 Bemis
SW SW NW Sec. 20-13-19W
Ellis County, Kansas

Operator: Mallonee Drilling Co., Inc.
 Contractor: Mallonee Drilling Co., Inc.
 Commenced: 9-29-53
 Completed: 10-13-53

Elev: 2085 KB
 D & A

<u>From</u>	<u>To</u>	<u>Description</u>	<u>Remarks</u>
0	40	Shale and gravel	
40	195	Shale	197 feet 8-5/8 surface casing set at 195 feet with 165 sacks 1% C.C. circulated.
195	550	Shale	
550	645	Sand and shale	
645	900	Shale	
900	1125	Sand	
1125	1275	Shale and sand	15051-0015 1-20-00
1275	1410	Shale	
1410	1455	Anhydrite	
1455	1520	Shale	
1520	1735	Shale and shells	
1735	2475	Lime and shale	
2475	2570	Lime	
2570	2765	Lime and shale	
2765	2845	Lime	
2845	3155	Lime and shale	
3155	3680	Lime	
3680	3720	Lime and shale	
3720	3734	Chert and lime	
3734	3745	Lime and shale	
3745	3778	Chert	
3778	3810	Lime	
3810 Total depth of hole			

Tops:

Topoka	3132	-1047
Heebner	3373	-1288
Teronte	3397	-1312
Lansing	3417	-1332
(Base K.C.)	3666	-1581
Conglomerate	3746	-1681
Arbuckle	3779	-1694
Rotary Total		
Depth	3810	-1725

PLUGGING
 FILE SEC. 20 T. 13 R. 19W
 BOOK PAGE 36 LINE 10

I certify that to the best of my knowledge and belief the above represents a true and accurate Driller's Log record of the above-captioned lease.

STATE GEOLOGICAL COMMISSION

OCT 30 1953

CONSERVATION DIVISION

Subscribed and sworn to before me this 16th day of October, 1953.

F. W. Mallonee
F. W. Mallonee

R. E. Mallonee
Notary Public