

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

15:051 30438 00 00  
WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:

Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217


Locate well correctly on above  
Section Plat

Ellis County, Sec. 22 Twp. 13 Rge. 19 (E) W (W)  
Location as "NE/CNW/KSW" or footage from lines NE NE SE  
Lease Owner Dreiling Oil, Inc.  
Lease Name Wiesner Well No. 1  
Office Address Rt. #2 Victoria, KS 67671  
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well  
Date well completed January 26, 19 74  
Application for plugging filed March 28 19 74  
Application for plugging approved March 29 19 74  
Plugging commenced June 18 19 74  
Plugging completed June 18 19 74  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production April 11, 19 74  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, KS  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3740 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Casing	0'	160'	8 5/8"	160'	0
	Casing	0'	3,740'	5 1/2"	3,740'	2,020'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pumped through 8 5/8" casing with plug and 2 sacks hulls, 20 sacks gel, 1 sack hulls, 50 sacks cement, 5 sacks gel, 50 sacks cement, maximum pressure 400# & shut in pressure 150#.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 2 1974  
CONSERVATION DIVISION  
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Dreiling Oil, Inc.  
Address Rt. #2 Victoria, KS 67671

STATE OF Kansas COUNTY OF Ellis, ss.  
Joe Hess, Sec. Treas. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
Joe Hess R.R. #2, Victoria, KS 67671  
(Address)

Subscribed and sworn to before me this 25th day of June, 19 74  
Cecilia Basgall  
Cecilia Basgall Notary Public.  
My commission expires September 13, 1976



**L. J. DREILING and SONS, Inc.**  
**VICTORIA, KANSAS**

**WELL LOG**

15 051 30438 00 00

Company Leo J. Dreiling Oil Company  
 Farm Route 2  
 Victoria, Kansas No. #1  
 Wiesner

Sec. 22 Twp. 13 Rng. 19

Location NE NE SE

Total Depth 3740'

County Ellis  
 2045' K.B.

Comm. 1-16-67 Comp. 1-26-67

Elevation: 2042' D. F.

Contractor L. J. Dreiling & Sons, Inc.  
 Route 2, Victoria, Kansas

2040' G. R.

Casing Record  
 160' 8 5/8"  
 3740' 5 1/2"

Cement Record  
 125 sks. Sunset cement  
 125 sks. salt cement  
 10 bbl. salt flush

Production: Producing Well

**Figures Indicate Bottom of Formations**

0'	160'	Top soil & shale
160'	376'	Shale
376'	408'	Sand
408'	818'	Shale
818'	1026'	Sand
1026'	1070'	Shale
1070'	1340'	Shale & Redbed
1340'	1390'	Anhy.
1390'	1620'	Shale & Shells
1620'	2050'	Shale & Lime
2050'	2380'	Shale & Lime
2380'	2600'	Shale & Lime
2600'	2805'	Shale & Lime
2805'	3007'	Lime & Shale
3007'	3160'	Shale & Lime
3160'	3235'	Lime
3235'	3303'	Lime & Shale
3303'	3408'	Lime
3408'	3420'	Lime
3420'	3460'	Lime & Shale
3460'	3483'	Lime
3483'	3530'	Lime
3530'	3550'	Lime
3550'	3605'	Lime
3605'	3650'	Lime
3650'	3740'	Lime
3740'	T.D.	

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAY 2 1974  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS )  
 )ss  
 COUNTY OF ELLIS )

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Weisner #1.

*Leo F. Dreiling*  
 LEO F. DREILING

Subscribed and sworn to before me this 27th day of January 1967.

*Joseph A. Hess*  
 JOSEPH A. HESS NOTARY PUBLIC

My commission expires: September 19, 1970