

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

WELL PLUGGING RECORD

15-051-23200-00-00

Give All Information Completely
 Make Required Affidavit

COUNTY Ellis SEC. 30 TWP. 13 RGE. 19W E/W
 Location as in quarters or footage from lines:

NW SW SW

Lease Owner Kimbark Oil Company

Lease Name Orth Well No. 1

Office Address Box 406, Ulysses, Kansas 67880

Character of Well (Completed as Oil, Gas or Dry Hole): Oil

Date Well Completed _____

Application for plugging filed _____

Plugging commenced November 4, 1983

Plugging completed December 8, 1983

Reason for abandonment of well or producing formation _____

Depleted

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt

Producing formation _____ Depth to top _____ bottom _____ T.D. 3859'

Show depth and thickness of all water, oil and gas formations. 8125/2

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	314'	None
				5-1/2"	3828'	2,970.35'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped 5 sacks cement on bottom, sanded to 3600' and dumped 5 sacks cement. Shot casing at 3000' and 2900'. Pulled 72 joints of 5-1/2" casing Squeezed well with 4 sacks hulls, 2 sacks gel, 25 sacks cement, 10 sacks gel, 1/2 sack hulls, 70 sacks cement, 8 sacks gel, 1/2 sacks hulls, released plug and pumped 70 sacks 50/50 Pozmix cement with 4% added gel and 3% calcium chlorldie. Max pressure 200 psi and shut in 50 psi.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF Kansas COUNTY OF Barton, ss.


James W. Rockhold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

James W. Rockhold Box 698, Great Bend, Ks.
 (Address) 67530

SUBSCRIBED AND SWORN TO before me this 12th day of December, 1983

My Commission expires:



Iona M. Leatherman
 Notary Public.

RECEIVED
 STATE CORPORATION COMMISSION

DEC 13 1983

CONSERVATION DIVISION
 Wichita, Kansas