


15-051-05131-00-00  
**WELL PLUGGING RECORD**

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Ellis County. Sec. 36 Twp. 13 Rge. 19 (E) W (W)  
Location as "NE/CNW&SW&" or footage from lines SW SE SW  
Lease Owner Fender Pipe & Supply  
Lease Name State X Well No. 1  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced Aug. 11 19 65  
Plugging completed Aug. 14 19 65  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Petty & Liker  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3840 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3840 feet to surface feet for each plug set.

Sanded up to 3350' dump 4 sacks of cement on bottom. Pulled pipe to 550' circ. mud. Pump 20 sacks of cement to 550'. Pulled pipe to 200' pump 20 sacks of cement. Pulled pipe out put 10 sacks on top. Well completed.

**RECEIVED**

STATE CORPORATION COMMISSION

SEP 9 1965

CONSERVATION DIVISION

Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnes & Sons Pipe Pulling Co.  
Address P.O. Box 313 Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.  
Allen T. Fender (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Allen T. Fender

Box 302 - Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 8<sup>th</sup> day of September, 19 65

My commission expires September 27, 1967  
Selma Underwood Notary Public.

CONTRACTOR'S WELL LOG 15-057-0513170-00

COMPANY: ARTNELL CO. & LEBEN DRILLING, INC.  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: STATE #1  
 LOCATION: SW SE SW SEC. 36-13S-19W  
 ELLIS COUNTY, KANSAS  
 COMMENCED: 8-6-57  
 COMPLETED: 8-23-57.

0	300	Shale & Shells	TOPSE	
300	890	Shale & Lime	Anhydrite	1450
890	1115	Sand	Heebner	3444
1115	1135	Shale	Toronto	3463
1135	1450	Shale & Redbed	Lansing-K.C.	3490
1450	1460	Anhydrite	Bs Kansas City	3762
1460	1498	Anhydrite	Conglomerate	3788
1498	1700	Shale	Arbuckle	None
1700	1865	Shale & Lime	RTD	3840
1865	2050	Shale		
2050	2590	Lime & Shale	Elevation 2190 K.B.	
2590	3020	Shale & Lime		
3020	3505	Lime & Shale		
3505	3730	Lime		
3730	3760	Lime & Shale		
3760	3762	Base of K.C.		
3762	3810	Cherty Conglomerate		
3810	3840	Conglomerate		
	<u>3840</u>	<u>Rotary Total Depth.</u>		

STATE OF KANSAS  
 STATE COMMISSIONER OF GEOL. & MINES

AUG 10 1957

MINING & REVENUE DIVISION  
 STATE OF KANSAS

Set 8 5/8" surface casing at 235' with 150 sacks cement & 3% CaCl.

I, James M. Battin, do hereby certify that the above and foregoing is a true and correct copy of the log of the State #1, SW SE SW of Section 36, Township 13 South, Range 19 West, Ellis County, Kansas, as reflected by the files of Leben Drilling, Inc.

LEBEN DRILLING, INC.

BY: James M. Battin  
 James M. Battin

STATE OF KANSAS )  
 COUNTY OF SEDGWICK) ss

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 13th day of September, 1957.

Ruth N. Benjamin  
 Ruth N. Benjamin - Notary Public

My commission expires June 17, 1961.