

WELL LOG

15-051-01157-00-00


Casing:

317' of 8 5/8 - 90 sx

Allan - #1 Pfeifer
 SW Corner SE $\frac{1}{4}$ -34-13-19W
 Ellis County, Kansas
 Commenced: 8/12/46
 Completed: 8/29/46
 Contractor - Tom Allan
 Elevation - 2195 L & S

- | | |
|---|---|
| <p>0 - 120 wht. chalk
 370 blue gumbo
 550 chalky shale
 680 dark sandy shale
 750 sandstone & pyrite
 810 shale & buff concretions
 850 pyrtic sand
 930 fine grain sandstone
 960 shale & concretions
 1190 amber sand
 1225 sandstone
 1508 red sandy grit
 1552 white anhydrite
 1700 red shale
 1850 shale
 2110 salt and shale
 2220 anhydrite
 2230 red shale
 2270 dolomite & shale
 2290 shale
 2330 dolomite
 2370 red shale
 2410 dolomite
 2450 lime
 2460 shale
 2480 lime
 2495 red shale
 2540 lime
 2550 shale
 2555 Brown chert
 2565 shale
 2595 lime
 2605 red shale
 2655 shale & shells
 2680 lime
 2708 red shale
 2720 soft oolitic lime
 2760 lime
 2780 red shale
 2805 lime
 2830 shale
 2845 lime
 3120 shale & shells</p> | <p>3150 lime
 3219 shale & shells
 3235 white lime
 3265 shale & shells
 3275 porous lime (water)
 3300 shale & shells
 3350 lime
 3357 shale
 3375 dense wht. Lithographic lime
 3410 shale & shells
 3475 lime
 3479 shale
 3483 coal black shale
 3492 shale & shell
 3508 red & gray shale
 3518 dense wht lime
 3530 red shale
 3532 dense wht lime
 3537 red & green shale
 3550 lime (V.S.S.O.)
 3560 shale, fossiliferous
 3572 lime
 3590 shale & shells
 3600 porous lime (water)
 3610 lime
 3620 porous lime (water)
 3625 lime (V.S.S.O.)
 3630 porous lime (water)
 3700 lime
 3705 oolitic lime (Pet. Res.)
 3725 lime
 3745 porous oolitic lime (water)
 3778 lime
 3806 shale & shells
 3813 soft red shale
 3828 white chert
 3843 green & maroon shale
 3860 red mud & varicolor chert
 3895 conglomerate of weathered
 oolitic chert
 4013 white chrystalline porous dolomite</p> |
|---|---|

34 13 19W
 70 16



WELL LOG (Con't.)

15-051-01157-00-00

Allan - #1 Pfeifer
SW Corner SE $\frac{1}{4}$ -34-13-19W
Ellis County, Kansas

Formations:

1508 Top Anhydrite
2370 Top Fort Riley
2708 Top Neva
3219 Top Topeka
3357 Top Lecompton
3530 Top Lansing
3843 Top Cherty Conglomerate
3895 Top Arbuckle

I certify that the above is a true and correct
copy of the well log on the above test.

Thomas H. Allan

Subscribed and sworn to before me this
4th day of September, 1946.

My Commission expires
June 14, 1950.

Oliver M. Stewart
Notary Public

