

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-051-02831-00-00

API NUMBER Drilled in 1958

LEASE NAME Orth

WELL NUMBER 1

330 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 30 TWP. 13 RGE. 19 (X or W)

COUNTY Ellis

Date Well Completed 1/9/58

Plugging Commenced 3-11-86

Plugging Completed 3-11-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR BHP Petroleum (Americas) Inc.

ADDRESS 925 Patton Road, Great Bend, KS 67530

PHONE#(316) 792-2756 OPERATORS LICENSE NO. 4655

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? no If not, is well log attached? yes

Producing Formation Lansing-Kansas City Depth to Top 3499 Bottom 3744 T.D. 3856
PBTD 3820

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing-Kansas City	Oil	3499	3744	10-3/4	500	0
Arbuckle	Oil	3838	3856	7	3838	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

50 sx of 60/40 poz w/10% gel and 150 lbs of hulls from 3577 to 3242'.

35 sx of gel w/150 lbs of hulls from 3242 to 1072. 7" wiper plug at 1072'.

160 sx of 60/40 poz w/10% gel & 150 lbs of hulls from 1072 to 0.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. 5287

Address Box 428 Hays, KS.

STATE OF Kansas COUNTY OF Ellis, ss.

Bill Wriston (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Bill Wriston *Bill Wriston*

(Address) 925 Patton Road, Great Bend, KS.

SUBSCRIBED AND SWORN TO before me this 4th day of April, 19 86

Ronald E. Row
Notary Public

My Commission Expires: My Appt. Exp. Sept. 9, 1987



APR - 8 1986

CONSERVATION DIVISION
Wichita, Kansas