


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15-051-01252-00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellis County. Sec. 4 Twp. 13S Rge. 20 (E) (W)
Location as "NE/CNW%SW%" or footage from lines SW SW NE
Lease Owner Kaiser, Francis and Leben Drilling, Inc.
Lease Name Erbert Well No. 1
Office Address 905 Central Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 12 1960
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 19
Plugging completed 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3914 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	262	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st plug set @ 540' w/ 20 sx cement
2nd plug set @ 180' w/ 15 sx cement
top plug set @ 40' w/ 10 sx cement

RECEIVED
STATE CORP. COMMISSION
MAR 21 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Leben Drilling, Inc.
Address 905 Central Building

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Frank Hamlin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Frank Hamlin
905 Central Bldg (Address)

SUBSCRIBED AND SWORN TO before me this 16th day of MARCH 1960

My commission expires April 23, 1963
Juanita M. Green Notary Public.



DRILLER'S LOG

COMPANY:
CONTRACTOR:
FAH:
LOCATION:
COMMENCED:
COMPLETED:

KAISER, FRANCIS AND LEBEN DRILLING, INC.
LEBEN DRILLING, INC.
HERBERT #1
SW SW NE SEC. 4-13N-20W
ELLIS COUNTY, KANSAS
2-29-60
3-12-60

0	75	Clay & Sand
75	85	Post Rock & Flint
85	100	Rock
100	262	Shale
262	795	Shale & Sand
795	970	Sand
970	1185	Sand
1185	1500	Shale & Red Bed
1500	1506	Shale & Red Bed
1506	1546	Anhydrite
1546	1725	Shale
1725	1815	Shale
1815	2040	Shale & Lime
2040	2370	Shale & Lime
2370	2605	Shale & Lime
2605	2940	Shale & Lime
2940	3300	Shale & Lime
3300	3485	Shale & Lime
3485	3540	Lime
3540	3570	Cherty Lime
3570	3590	Lime
3590	3698	Lime
3698	3770	Lime
3770	3820	Lime & Chert
3820	3845	Lime
3845	3905	Lime & Chert
3905	3914	Lime & Chert
	<u>3914</u>	<u>Rotary Total Depth D & A</u>

Set 8 5/8" surface casing @ 262' w/ 175 sacks Sunset cement.

I, Frank Hamlin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Herbert #1, located SW SW NE of Section 4, Township 13 South, Range 20 West, Ellis County, Kansas, as reflected by the files of Leben Drilling, Inc.

Frank Hamlin

Frank Hamlin

STATE OF KANSAS }
COUNTY OF SEDGWICK } SS:

RECEIVED
STATE OF KANSAS

MAR 21 1960

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 16th day of March, 1960.

NOTARY DIVISION
Topeka, Kansas

Juanita M. Green

Juanita M. Green, Notary Public

My Commission Expires:
April 23, 1963