

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 11 1962
CONSERVATION DIVISION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Petroleum Inc 15651-02863-0040
Complete Address: R. R. #2 Great Bend, Kansas
Lease Name Werth Well No. 2
Location SE SW NW Sec. 2 Twp. 13 Rge. (E) (W) 20
County Ellis Total Depth 3873
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated: _____
Plugging Contractor: Morgan Pipe Pulling Service
Address: Hutchinson, Kansas License No. 43
Operation Completed: Hour 10AM Day 3 Month 11 Year 62

The Above well was plugged as follows:

8 5/8" 580' circulated with cement - 5 1/2" 3870' with 100 sax cement - perforated 3835'

Filled with sand to 3820', set 4 sax cement with dump bailer - pulled

2600' 5 1/2" to 580' - circulated hole with heavy gel mud through 5 1/2" at

580' (30 sax Gel) - displaced 20 sax cement through 5 1/2" at 580' - heavy

mud to 180' - displaced 20 sax cement through 5 1/2" at 180', heavy mud to

35', set bridge and filled to bottom cellar with cement.

Mudding and cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 11/7/62

INV. NO. 5962-W