

KANSAS

Form CP-3
Rev. 6-26-62

59

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
AUG 21 1967
CONSERVATION DIVISION
Wichita, Kansas

15-051-20103-00-00

Operator's Full Name H. B. Mabee Company

Complete Address: Box 94718 Oklahoma City, Oklahoma

Lease Name Meis Well No. 1

Location NW NW NE Sec. 22 Twp. 13 Rge. 19 (E) (W) X

County Ellis Total Depth 3740'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: L. J. Dreiling & Sons, Inc.,

Address: Victoria, Kansas License No.

Operation Completed: Hour 4:15 P Day 15 Month 8 Year 1967

The Above well was plugged as follows:

RTD 3740' 8 5/8 csg set at 138' cwc 100 sc.
Gunned pits, circulated heavy mud, set cementing plug at 680' and displaced 100 sc cem.
thru drill pipe. Heavy mud to 150' set cementing plug and displaced 25 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 8-21-67

INV. NO. 6164-W