

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 20 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-051-30438-00-00

Operator's Full Name Dreiling Oil, Inc.
Complete Address R. R. #2 Victoria, Kansas
Lease Name Weisner Well No. 1
Location NE NE SE Sec. 22 Twp. 13 Rge. (E) (W) 19
County Ellis Total Depth 3740'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.

Operation Completed: Hour 10 A Day 18 Month 6 Year 1974

The above well was plugged as follows:

Total Depth 3740' 8 5/8 csg set at 160' cwc 125 sk.
5 1/2 csg set at 3740' cw 125 sk cmt. Perf. (3337'-3340')
Set 5 1/2 wood plug at 3300' -poured 50 gal sand -dumped 4 sk cmt W/dump bailer.
Cutoff and recovered 2020' of 5 1/2 csg.
Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls -550 sk cmt -5 sk
gel & water -released 8 5/8 plug and pumped 50 sk cmt by Sun Cementing Co.
PP 400 lbs, SIP 150 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey
Well Plugging Supervisor

DATE 6/21/74
INV. NO. 9338-W