

K  
KANSAS  
STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

15-051-1938700.00

**RECEIVED**  
STATE CORPORATION COMMISSION

AUG 21 1962

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Kansas Exploration Co  
Complete Address: 232 Bonnie Brae Wichita, Kansas  
Lease Name Kans State Well No. 1  
Location 20' E SE SW SW Sec. 36 Twp. 13 Rge. (E) (W) 19  
County Ellis Total Depth 3860  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A x  
Other well as hereafter indicated:         
Plugging Contractor: Leben Drg Co  
Address: Wichita, Kansas License No.         
Operation Completed: Hour 8:30PM Day 17 Month 8 Year 62

The Above well was plugged as follows:

8 5/8" 240' circulated with cement.

Circulated hole with heavy mud, set cementing plug at 590', displaced 20 sac  
cement through drill pipe, heavy mud to 235', set plug, hulls and 20 sac  
cement, heavy mud to 35', set plug, 1/2 hulls and filled to bottom cellar  
with cement.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**  
DATE 8/22/62  
INV. NO. 5567-W

Signed: *Edmond Perry*  
Well Plugging Supervisor