

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 17 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-051-05131-00-00

Operator's Full Name Fender Pipe & Supply

Complete Address: Box 302 Russell, Kans

Lease Name _____ State X Well No. 1

Location SW SE SW Sec. 36 Twp. 13 Rge. (E) (W) 19

County Ellis Total Depth 3840

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Plugging Contractor: Barnes & Sons

Address: Russell, Kans License No. 9

Operation Completed: Hour 3pm Day 14 Month 8 Year 65

The Above well was plugged as follows:

8 5/8 250' circulated with cement - 5 1/2" 5570' with 100 sax cement

PB to 3380' sand to 3350', set 4 sax cement with dump bailer.

Pulled 2680' 5 1/2" to 550' circulated hole with heavy gel mud through

5 1/2" - displaced 20 sax cement through 5 1/2" at 550', heavy mud to

200' displaced 20 sax cement through 5 1/2" at 200', heavy mud to

35' set rock and 10 sax cement to bottom cellar.

Mudding and cementing by Halliburton Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 8/17/65

INV. NO. 1644-W