

F

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 051- 21,598-0000 (of this well)

Operator's Full Name Arapaho Petroleum, Inc.

Complete Address 1700 Security Life Bldg., Denver, Colorado

Lease Name Velma F. Turner Well No. 34-1

Location C SW SW Sec. 34 Twp. 13 Rge. (E) (W) 19

County Ellis Total Depth 3940'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Rains & Williamson

Address Wichita, Kansas License No.

Operation Completed: Hour 8:30 A Day 18 Month 12 Year 1978

The above well was plugged as follows:

RTD 3940' 8 5/8 csg set 250' cwc 150 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 720' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

DEC 20 1978

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 12-26-78
INV. NO. 8788.0