

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

NOV 27 1967
11-27-67
CONSERVATION DIVISION
Wichita, Kansas

15-051-2061-00-00

Operator's Full Name Clinton Oil Company

Complete Address: 6810 W. Highway 54 Wichita, Kansas

Lease Name Erbert Well No. V-1

Location SW NE NE Sec. 4 Twp. R3 Rge. 20 (E) (W) X

County Ellis Total Depth 3954

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Garvey Drlg. Co.

Address: Wichita, Kansas License No. _____

Operation Completed: Hour 2 A Day 24 Month 11 Year 1967

The Above well was plugged as follows:

RTD 3954 8 5/8 csg set at 251' cwc.
Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 100 sc cem.
thru drill pipe. Heavy mud to 240' set cementing plug and displaced 25 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Res? M...
Well Plugging Supervisor

DATE 11-28-67

INV. NO. 6763-W