


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Ellis County. Sec. 21 Twp. 11S Rge. 17(W)
Location as "NE/CNW/SW" or footage from lines 330' fr. N & 1270' fr. W Lines of
Lease Owner Phillips Petroleum Company S/2 NE/4
Lease Name F. A. Bemis Well No. 3
Office Address Box 779, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed December 20, 1956
Application for plugging filed October 9, 1956
Application for plugging approved October 10, 1956
Plugging commenced November 5, 1956
Plugging completed November 8, 1956
Reason for abandonment of well or producing formation Uneconomical to operate

If a producing well is abandoned, date of last production June 14, 1956
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation Arbuckle Depth to top 3363 Bottom NR Total Depth of Well 3389 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Anhydrite	Dry	1061	1100	16"	62'	None
Topeka	Dry	2800	NR	10-3/4"	1083'	None
Lansing-Kansas City	Dry	3060	NR	7"	3387'	2404'
Simpson	Dry	3337	3357			
Simpson Detrital	Dry	3357	3363			
Arbuckle	Oil	3363	3389			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped sand to 3364'. Filled with sand from 3364' to 3339'. Dumped 5 sx. cement to 3321'. Mudded hole from 3321' to 300'. Set 10' rock bridge and 32 sx. cement to 226'. Mudded hole to 46'. Set 10' rock bridge and 18 sx. cement in filling to base of cellar. Well plugged and abandoned at 2:30 P.M. 11-8-56. FINAL REPORT.

RECEIVED
STATE CORPORATION COMMISSION
NOV 10 1956
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
A. J. Willis (employee of owner) ~~not a member of the~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 779, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of November, 19 56

[Signature]
Notary Public.

My commission expires November 18, 1957

PLUGGING
FILE SEC. 21 T. 11 R. 17W
BOOK PAGE 106 LINE 62

EXPLORATION RECORD

-Phillips Petroleum Company - F. A. Bemis #3 - 330' from North and 1270' from West Lines,
S/2 NE/4 Sec. 21-11S-17W, Ellis County, Kansas.

Lease F. A. BemisWell 3

Formation Name	Top	Base	Remarks
Shale and shells	0	400	
Sand and iron	400	500	
Iron	500	540	
Shale and iron	540	590	
Sand	590	715	
Shale and shells	715	760	
Shale and redbed	760	860	
Shale	860	990	
Redbed and lime	990	1050	
Shale	1050	1061	
Anhydrite	1061	1100	
Shale	1100	1240	
Shale and shells	1240	1405	
Shale	1405	1430	
Salt	1430	1630	
Lime	1630	1645	
Lime - Broken	1645	1740	
Shale	1740	1775	
Lime	1775	1970	
Lime and shale	1970	2205	
Lime	2205	2230	
Sand	2230	2250	
Lime and shale	2250	2290	
Shale and shells	2290	2350	
Shale and lime	2350	2445	
Shale	2445	2575	
Lime - Hard	2575	2604	
Lime	2604	2705	
Lime and shale	2705	2780	
Hard Lime	2780	2797	
Lime	2797	2862	
Hard Lime	2862	2888	
Lime	2888	2922	
Hard Lime	2922	2937	
Lime	2937	2958	
Shale	2958	2980	
Lime	2980	3325	
Shale	3325	3345	
Sand and Lime	3345	3348	
Lime	3348	3349	
Sand and shale - Hard	3349	3354	
Siliceous Lime	3354	3389	

PLUGGING

FILE SEC. 21 T. 11 R. 17W
BOOK PAGE 106 LINE 62

RECEIVED
OCT 10 1953
OIL & GAS DIVISION
KANSAS DEPARTMENT OF REVENUE