

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 Wichita State Office Bldg.
 130 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-051-22,084 0000

LEASE NAME Bemis "A"

WELL NUMBER 6

4260 Ft. from S Section Line

300 Ft. from E Section Line

SEC. 21 TWP. 11S RGE. 17 ~~W~~ (W)

COUNTY Ellis

Date Well Completed 12-30-81

Plugging Commenced 3-7-96

Plugging Completed 3-7-96

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR ROBERT R. PRICE OPERATING, INC.

ADDRESS P. O. Box 470442, Tulsa, OK 74147

PHONE 918 1492-1694 OPERATORS LICENSE NO. 6273

Character of Well Oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by District #4 staff (XCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Arb. & KC Depth to Top 3302' Bottom 3455' T.D. 3972'

4080 POB
XCC

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle	Oil & Water	Surf.	297'	8 5/8"	297'	
KC	Oil & Water	Surf.	4020'	5 1/2"	4030'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug was used, state the character of same and depth placed, from _____ feet to _____ feet each set 5 1/2" casing previously squeezed @ 635' w/150 sx to maximum pressure of 1500#. Squeezed down 5 1/2" casing with 250 sx of cement blend with 500# of hulls mixed in to a maximum pressure of 900#. Shut in pressure was standing @ 450# 250 sx 60/40 pozmix - 10% gel - 500# hulls

Name of Plugging Contractor Allied Cementing, Inc License No. _____
 Address Russell, KS

RECEIVED
 STATE CORPORATION COMMISSION
06-03-96
 JUN 03 1996

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Robert R. Price Operating, Inc.

STATE OF Oklahoma COUNTY OF Tulsa, ss.


CONSERVATION DIVISION
 WICHITA, KS

ROBERT R. PRICE (Employee of Operator) or (~~Contractor~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 470442, Tulsa, OK 74147

SUBSCRIBED AND SWORN TO before me this 22nd day of May, 19 96



Rachel D Patterson
 Notary Public

Ex. Pres: 02-26-98