


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Location as "NE/CNW/SW" or footage from lines Ellis County, Sec. 21 Twp. 11 Rge. 17 (E) (W)  
NW NE SE  
Lease Owner Morganstern & Spector  
Lease Name Bemis #8 Well No. \_\_\_\_\_  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed 11-5-37 19\_\_\_\_  
Application for plugging filed May 28, 1959 19\_\_\_\_  
Application for plugging approved May 29, 1959 19\_\_\_\_  
Plugging commenced 6/12/59 19\_\_\_\_  
Plugging completed 6/19/59 19\_\_\_\_  
Reason for abandonment of well or producing formation failure to produce profitably  
If a producing well is abandoned, date of last production March 1959  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Arbuckle Depth to top 3370 Bottom 3388 Total Depth of Well 3455 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				16"	85'	none
				10 3/4" OD	1081'	none
				7" OD	3370'	1893.47
				4 1/2"	3475'	2221.04

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.  
Plugged back with sand to 3460 ft. Circulated mud 450 ft. Pumped 25 sacks cement at 450 ft. Pumped 25 sacks cement at 180 ft. Set rock bridge & dumped 10 sacks cement.

RECORDED  
STATE CORPORATION COMMISSION  
AUG 10 1959  
CONSERVATION DIVISION  
Wichita, Kansas  
08-10-59

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor E & L Casing Pulling Co.  
Address 1416 Coolidge Great Bend, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.  
Morganstern & Spector (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Morganstern & Spector  
(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 7th day of August, 19 59

My commission expires December 1, 1959  
Elsie Coady  
Elsie Coady Notary Public.

PLUGGING  
FILE SEC. 21 T. 11 R. 17W  
BOOK PAGE 40 U. 41


CITIES SERVICE OIL CO.  
Bemis No. 8.

SEC. 21 T. 11 R. 17W  
NW NE SE  
330' S. 993.3' W of E/4 Cor.

DEEP WELL RECORD

County. Ellis

Total Depth. 3455' SLM  
Comm. 10-8-37 Comp. 11-5-37  
Shot or Treated.  
Contractor. John E. Mabco.  
Issued. 5-20-50



Elevation.

CASING:  
16 " 85'  
10 3/4 " 1081'  
7 " 3370' SLM

Production. 38 bbls. Per. 1955  
38 bbls. Per. 1956

Figures Indicate Bottom of Formations.

surface shalo	76
shalo & shells	186
sand, shalo & shells	200
shalo & shells	975
shalo, shells & red beds	1065
shalo & shells	1090
anhydrite	1120
red beds	1134
red beds, shalo & shells	1338
shalo, shells & salt	1563
shalo & shells	1951
lime & shalo	2404
shalo & shells	2655
lime & shalo	2836
lime	2905
lime & shalo	2940
lime	2972
lime & shalo	3300
lime	3358
lime & shalo	3367
shalo, sand & conglom- merate	3372
SLM Corr. 3372 equals	3369
lime (corod)	3374
SLM Corr. 3374 equ ls	3372
lime	3388
Total Depth.	

WELL LOG BUREAU  
CITIES SERVICE OIL CO.  
Comm. 10-8-37  
Comp. 11-5-37  
Contractor: John E. Mabco.  
Production: 38 bbls. Per. 1955  
38 bbls. Per. 1956  
Drilled to depth of 3455'  
Produced 38 bbls. Per. 1955-1956  
7' of sand in 11' zone.  
Shale in 10' zone.

**RECEIVED**  
STATE COMMISSION

MAY 27 1959

REGISTRATION DIVISION  
Wichita, Kansas

Top Siliceous 3370' SLM  
Penetration 18'  
Total Depth. 3388'

First pay 3372-77  
Second pay 3379-85

**PLUGGING**  
FILE SEC 21 T. 11 R. 17W  
BOOK PAGE 11: 11