

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-051-05798-0000

API NUMBER 8-30-40
 LEASE NAME Hadley
 WELL NUMBER 3

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

2970 Ft. from S Section Line
8970 AUB YCC
 S $\frac{1}{2}$ SE NW Ft. from E Section Line

02-21-91
 FEB 21 1991

LEASE OPERATOR Berexco
 ADDRESS Box 723 Hays, Kansas 67601
 PHONE#(913) 628 6101 OPERATORS LICENSE NO. 5363
 Character of Well Oil

SEC. 21 TWP. 11 RGE. 17 (E) or (W)
 COUNTY Ellis
 Date Well Completed 8-30-40
 Plugging Commenced 2-15-91
 Plugging Completed 2-18-91

(Oil, Gas, D&A, SMD, Input, Water Supply Well)
 The plugging proposal was approved on 2-18-91 (date)
 by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, Is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3412

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	surface	0	101	13		none
	Casing	0	8364	7		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Drilled to 1450'. Spot 200 gallon 15% regular acid. Let set. Try drilling. Won't go.
Pull tubing. Perf. 1150 and 535'. Run 44 its. to 1443'. Mix 200 sk. Pull 30 its. to 450'
Mix 25 sk. 60/40 8% oil. Circulate to surface. Pull tubing. Mix 15 sk. down surface. Shut
in at 200#. Mix 135 sks. down 7". Shut in at 350#.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Berexco License No. 5363

Address Rox 723 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco

STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

ROSEMARY SMITH
 NOTARY PUBLIC
 STATE OF KANSAS
 MY APPT. EXP. MAY 1, 1991

(Signature) Ted Crawford
 (Address) Box 723 Hays, Kc.
30 day of February, 19 91
Rosemary Smith
 Notary Public

My Commission Expires: 5-1-1991