

1080223
TO: STATE CORPORATION COMMISSION

10-19

API NUMBER 15-075-20,330 ⁰⁵⁰⁰
C NE SEC. 17, T 22 S, R 40 W

CONSERVATION DIVISION - PLUGGING SECTION 1320 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1320 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME HCU WELL # 1720-B

TECHNICIAN'S PLUGGING REPORT COUNTY HAMILTON

OPERATOR LICENSE # 31321 WELL TOTAL DEPTH 2800 ^{91.00} FEET

OPERATOR: LOUIS DREYFUS NATURAL GAS PRODUCTION CSG: SIZE 4 1/2 " FEET 2800

NAME AND 14000 QUAIL SPRINGS PKWY STE 600 SURFACE CASING: SIZE 8 5/8" FEET 222'

ADDRESS OKLAHOMA CITY, OK 73134

ABANDONED OIL WELL GAS WELL INPUT WELL INJ WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 2:30 PM DAY: 19 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM MANNY BOATWRIGHT

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: PERFS AT 2715-2720 4 1/2" CASING AT 2800' WITH 550 SX CEMENT

1ST PLUG SAND BACK TO 2650' WITH 4 SX CEMENT ON TOP.

2ND PLUG RUN TUBING TO 1025' CIRCULATE CEMENT TO SURFACE. 10-22-98

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 4:30 PM DAY: 19 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG SANDED BACK TO 2650' WITH 4 SX CEMENT ON TOP.

2ND PLUG RAN TUBING TO 1025' IN 4 1/2" CIRCULATED CEMENT TO SURFACE WITH 60 SX CEMENT.

PULLED TUBING. PULLED 20' IF 4 1/2" RAN BACK IN WITH 32' 2 3/8" JT. CIRCULATED CEMENT TO

SURFACE WITH 15 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 20' OF 4 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Kevin P. Strube
(TECHNICIAN) FORM CP-2/3

10-23-98
60172