

040318

9-11

56

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION App.  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 007-20,792 6000

NE NW NW, SEC. 10, T 35 S, R 10 W/E

4780 feet from S section line

4480 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6006

Lease Name Schrock "A" Well # 1

Operator: Molz Oil Company

County Barber

Name & Address RFD #2, Box 54

Well Total Depth 5183 feet

Kiowa, KS 67070

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 10 3/4 feet 239

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 1:30 p.m. Day: 11 Month: 9 Year: 19 89

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 5171' Open hole at 5171-5183'

1st plug sand back to 5120' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release

wiper plug and pump 130 sx cement.

RECEIVED  
9-18-89  
SEP 18 1989

Plugging Proposal Received by Mike Wilson  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:15 p.m. Day: 11 Month: 9 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back from 5183-5100' and put 4 sx cement on top of  
sand bridge with bailer,

2nd plug pumped down 10 3/4" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement,  
10 sx gel, 100 lbs. hulls, and 130 sx cement.

Maximum pressure 900 psi and shut in 600 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 4200' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-22-89

INV. NO. 25938

9-11

Signed Stephen J. Pfeiffer  
(TECHNICIAN)