

To: 1060724
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

APJ NUMBER 15-007-22,091 0000
150E of
SE NW, SEC. 10, T 35 S, R 10 W10
3300 feet from S section line
3150 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License 15363
Operator: Beredec Inc.
Name &
Address 970 1/2 th Financial Center
Wichita, Kansas
67202

Lease Name Schupbach Well # 1
County Barber 174.20
Well Total Depth 5360 (Impress)
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 313

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated (anhydrite 1520' to 1600') (Elev. 1271 G.S.)

Plugging Contractor Beredec, Inc. License Number 5147

Address Wichita, Kansas 67202

Company to plug at: Hour: 7:00AM Day: 9 Month: November Year: 19 85

Plugging proposal received from Gary Marschall

(company name) Beredec Inc. (phone) 316-265-3311

were: 1st plug @ base of the anhydrite w/ 50 sbx cement.
2nd plug @ bottom surface pipe w/ 40 sbx cement
3rd plug @ 40' on solid bridge & circulate 10 sbx cement to 0' through drill pipe
4th plug circulate 10 sbx cement in rat hole & 10 sb cement in mouse hole.

Plugging Proposal Received by Paul A. Luttin
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 10:45AM Day: 9 Month: November Year: 19 85

ACTUAL PLUGGING REPORT 1st plug @ 1600' w/ 50 sbx cement.

2nd plug @ 340' w/ 40 sbx cement.
3rd plug @ 40' on solid bridge w/ 10 sbx cement circulate through
drill pipe. 4th plug circulate 10 sbx cement in rat hole &
10 sbx cement in mouse hole.

B.J. Titan pumped 60/40 poss w/ 6% gel through drill
Remarks: pipe w/ hole full of heavy mud.
(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED
STATE CORPORATION COMMISSION

DATE 12-9-85
INV. NO. 11326

NOV 18 1985
11-18-85
CONSERVATION DIVISION
Wichita, Kansas

Signed Paul A. Luttin
(TECHNICIAN)