

4-061207

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-051-25,013-0000
164' SW of
SE NW /4 SEC. 35, 13 S, 19 W
3200 feet from S section line
3430 feet from E section line

Operator license# 30606
Operator: Murfin Drilling Company
Address: 250 N. Water - Suite #300
Wichita, Kansas 67202

11/17

Lease: Younger-Dinges Unit Well # 1-35
County: Ellis 127.04
Well total depth 3909 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 233 feet

Aband. oil well___, Gas well___, Input well___, SWD___, D & A X

Plugging contractor: Murfin Drilling Company, Inc. License# 30606

Address: 250 N. Water - Suite #300 - Wichita, Kansas 67202

Company to plug at: Hour: 1:00 P.M. Day: 17 Month: November Year: 1999

Plugging proposal received from: Rodney Farr

Company: Murfin Drilling Company, Inc. Phone: 316-267-3241

Were: Order 215 sxs 60/40 posmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour 4:15 A.M., Day: 17, Month: November, Year: 1999

Actual plugging report:
1st. Plug at 3780' w/25 sxs cement. Arbuckle 3790'.
2nd. Plug at 1510' w/ 25 sxs cement. Anhydrite 1480' - 1519'.
3rd. Plug at 785' w/100 sxs cement. Dakota 484' - 784'.
4th. Plug at 285' w/40 sxs cement. Surface pipe to 233'.
5th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

Remarks: Allied Cementing.
Condition of casing in hole): GOOD X BAD___ Anhy.plug: YES___ X___ NO___
Bottom plug(in place): YES X, CALC___, NO___ Dakota plug: YES X, NO___
Plugged through TUBING___, CASING___ Elevation: 2184 GL

I did[] / did not[X] observe the plugging.

[Signature]
(agent)
Form CP-2/3

STATE OF KANSAS CONSERVATION DIVISION

NOV 24 1999
CONSERVATION DIVISION
WICHITA, KANSAS

(R)

INVOICED

DATE 12/7/99
INV. NO. 60928