

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25155-00-00
Spot: S2SESWNW Sec/Twnshp/Rge: 33-13S-19W
2730 feet from S Section Line, 4880 feet from E Section Line
Lease/Unit Name: DOROTHY Well Number: 33-1
County: ELLIS Total Vertical Depth: 3995 feet

Operator License No.: 32511
Op Name: IMPERIAL AMERICAN OIL CORPORATI
Address: 303 N. CARROLL BLVD., #214
DENTON, TX 76201

Conductor Pipe: Size feet: \$129.84
Surface Casing: Size 8.625 feet: 559
Production: Size feet:
Liner: Size feet:

Well Type: DH UIC Docket No: Date/Time to Plug: 08/30/2002 9:45 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Revd. from: BILL WYNN Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Order 215 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 08/30/2002 11:45 PM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 3900' w/25 sxs.
2nd. Plug at 1575' w/25 sxs. Anhydrite 1558' - 1597'.
3rd. Plug at 950' w/100 sxs. Dakota 557' - 857'.
4th. Plug at 610' w/40 sxs. Surface pipe at 559'.
5th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

RECEIVED

SEP 05 2002

KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed


(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 9-6-02

INV. NO. 2003060480

SEP 03 2002