

4-061238

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-051-25,036-0000

NW SW SW /4 SEC. 33 , 13 S, 19 W
950 feet from S section line
480 feet from W section line

Operator license# 32511

8/20

Lease: Bemis Well # 1-33

Operator: Imperial American Oil Corp.

County: Ellis 130.00

Address: 10004 W. 20th St. N.
Wichita, Kansas 67212

Well total depth 4000 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 511 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Murfin Drilling License# 30606

Address: Wichita, Kansas 67202

Company to plug at: Hour: 7:00 A.M. Day: 20 Month: August Year: 2000

Plugging proposal received from: Ed McKenna

Company: Murfin Drilling Phone:

Were: Order 225 sxs 60/40 posmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour 10:30 A.M., Day: 20, Month: August, Year: 2000

Actual plugging report:

1st. Plug at 1550' w/25 sxs cement. Anhydrite 1528' - 1572'.

2nd. Plug at 950' w/100 sxs cement. Dakota 538' - 838'.

3rd. Plug at 575' w/40 sxs cement. Surface pipe to 511'.

4th. Plug at 40' w/10 sxs.

Rathole with 15 sxs.

Mousehole with 10 sxs.

RECEIVED
STATE CORPORATION COMMISSION
SEP 05 2000

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Allied Cementing.

Condition of casing in hole): GOOD X BAD Anhy.plug: YES X NO

Bottom plug(in place): YES X, CALC , NO X Dakota plug: YES X, NO

Plugged through TUBING , CASING . Elevation: GL

I did[] / did not[X] observe the plugging.

[Signature]
(agent)

INVOICED
DATE 9/11/00
INV. NO. 2001060633

Form CP-2/3

[Signature]