

4-070076

11-5

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-051-24,544-0000

NE NE SE /4 SEC. 01, 13 S, 20 W  
2310 feet from S section line  
330 feet from E section line

Operator license# 5285

Lease: Schuster Well # 1

Operator: The Dane G. Hansen Trust

County: Ellis 128.38

Address: P.O. Box 187  
Logan, Kansas 67646

Well total depth 3950 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 263 feet  
W/150 sxs.

ABAND. oil well X, Gas well, Input well, SWD., D&A

Plugging contractor: Dane G. Hansen License# 5285

Address: P.O. Box 187 - Logan, Kansas 67646

Company to plug at: Hour: 10:00 A.M. Day: 5 Month: November Year: 1997

Plugging proposal received from: Richard L. Wallgren Sr.

Company: Dane G. Hansen Phone: 785-689-4816

Were: 5 1/2" casing set at 3800' w/top 175 sxs - bottom 355 sxs. PBSD 3800'.  
Perfs 3483' - 3683'. Anhy at 1522'.  
Ordered 200 sxs 60/40 pozmix - 10% gel with 500# hulls.

Plugging Proposal Received by: Herb Deines  
Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 11:30 A.M., Day: 5, Month: November, Year: 1997

Actual plugging report: Halliburton pumped 32 sxs Mid Con II at 11.2# per gallon with 200# hulls - 20 sxs gel with 300# hulls - 49 BBLs. Topped off with 82 sxs of Mid Con II at 11.2# per gallon - 45 BBLs - slurry. Max. P.S.I. 900#. S.I.P. 400#. Hooked up to 8 5/8" annulus. S.I.P. 800#.

Remarks: Cement in braden head.  
Condition of casing(in hole): GOOD BAD X  
Bottom plug(in place): YES X, CALC, NO  
Plugged through TUBING, CASING X  
Anhy.plug: YES X NO  
Dakota plug: YES X NO  
Elevation: 2182 GL

I did [ X ] / did not [ ] observe the plugging.

Richard Williams  
(agent)

RECEIVED  
KANSAS CORPORATION COMMISSION

Form CP-2/3

INVOICED

DATE 11-14-97

INV. NO. 49499

NOV 07 1997

CONSERVATION DIVISION  
WICHITA, KS