

11-5  
4-070077

TO:

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-051-24,523-0001

SE NE SE /4 SEC. 01, 13 S, 20 W  
1650 feet from S section line  
330 feet from E section line

Operator license# 5285

Lease: Schuster Well # 2

Operator: The Dane G. Hansen Trust

County: Ellis 127.27

Address: P.O. Box 187  
Logan, Kansas 67646

Well total depth 3916 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 223 feet  
W/135 sxs.

ABAND. oil well ☒, Gas well ☐, Input well ☐, SWD. ☐, D&A ☐

Plugging contractor: Dane G. Hansen License# 5285

Address: P.O. Box 187 - Logan, Kansas 67646

Company to plug at: Hour: 11:30 A.M. Day: 5 Month: November Year: 1997

Plugging proposal received from: Richard L. Wallgren Sr.

Company: Dane G. Hansen Phone: 785-689-4816

Were: 5 1/2" casing set at 3848' w/top 355 sxs - bottom 200 sxs. PBTD 3800'.  
Perfs 3490' - 3713'. Anhy at 1520'.  
Ordered 200 sxs 60/40 pozmix - 10% gel with 500# hulls.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All ☒ , Part ☐ , None ☐

Completed: Hour: 12:30 P.M., Day: 5, Month: November, Year: 1997

Actual plugging report: Halliburton pumped 32 sxs Mid Con II at 11.2# per gallon with 200#  
hulls - 20 sxs gel with 300# hulls - 49 BBLs. Mixed 82 sxs of Mid Con II at 11.2# per gallon.  
Total 45 BBLs - slurry. Max. P.S.I. 900#. S.I.P. 250#.  
Checked 8 5/8" annulus - pressured up to 600#.

Remarks: Cement in braden head.

Condition of casing(in hole): GOOD ☐ BAD ☒ Anhy plug: YES ☒ NO ☐  
Bottom plug(in place): YES ☒ , CALC ☐ , NO ☐ Dakota plug: YES ☒ , NO ☐  
Plugged through TUBING ☐ , CASING ☒ . Elevation: 2183 GL

I did ☒ / did not ☐ observe the plugging.RECEIVED  
KANSAS CORPORATION COMMISSION (agent)

Form CP-2/3

INVOICED

NOV 07 1997

DATE 11-14-97

INV. NO. 49500

CONSERVATION DIVISION  
WICHITA, KS