

1-21

6 070745

API NUMBER 15- 051-24,577-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW NW SE, SEC. 1, T 13 S, R 20 W/E

1650 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

RCW
1-26-89

Operator License # 5285

Lease Name Schuster Well # 3

Operator: The Dane C. Hansen Trust
Name & Address Box 187

County Ellis 126.75

Well Total Depth 3900 feet

Logan, Ks. 67646

Conductor Pipe: Size 0 feet

Dane G. Bales

Surface Casing: Size 8 5/8 feet 256

Abandoned Oil Well Gas Well Input Well SWD Well U&A

Other well as hereinafter indicated

Plugging Contractor Galloway Drilling Co. License Number 5783

Address 340 Broadway Plaza 1055 Broadway Wichita, Ks.

Company to plug at: Hour: PM Day: 21 Month: Jan Year: 19 89

Plugging proposal received from Carl McGuire

(company name) Calloway Drilling Co. Inc. (phone)

were: Arbuckle Well at 3880' Elv. 2146' Anh 1478'; No circulation problems. Mud conditions 41 viscosity; 9.5 weight; 11.8 water loss. 8 5/8" 256' S.P. cwc w/150 sks

60/40 Poz 2% Gel 3% Cal Cl by Allied Cement. Proposal 225 60/40 Poz 6% Gel 3% Cal Cl and

8 5/8" plug. Spot with drill stem, circulate heavy mud between all plugs. 25 sks at 3800'

25 sks at 1500'; 100 sks w/1 sk Celloflake at 720'; 50 sks at 300'; Hulls plug at 40'

w/10 sks cement 15 sks rathole (circ) Plugging Proposal Received Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 5:15PM Day: 21 Month: Jan Year: 19 89

ACTUAL PLUGGING REPORT Ordered 225 sks 60/40 Poz 6% Gel 3% Cal Cl and 8 5/8" plug.

Spotted with drill stem, circulated heavy mud between all plugs. 1st plug at 3800' w/

25 sks cement. 2nd plug at 1500' w/25 sks cement.

3rd plug at 720' w/100 sks cement w/1 C.F.

4th plug at 300' w/50 sks cement.

5th plug Hulls plug at 40' w/10 sks cement. 15 sks in rathole (circulate) Cemented by Allied Cement.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-30-89

INV. NO. 23814 1-21

JDS

Signed Marion J. Schmidt (TECHNICIAN)