

4 060187

4-13

322

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-051-24,735-00-00

W2 SE NE, SEC. 1, T 13 S, R 20 W/E

3300 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5285

Lease Name Schuster "A" Well # 2

Operator: Dane G. Hansen Trust

County Ellis 126.91

Name & Address P.O. Box 187

Well Total Depth 3905 feet

Logan, KS 67646

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 258

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXX

Other well as hereinafter indicated

Plugging Contractor Galloway Drilling Co. License Number 5783

Address Wichita, KS

Company to plug at: Hour: 10:00AM Day: 13 Month: April Year: 19 91

Plugging proposal received from Carl McGuire

(company name) Galloway Drilling Co. (phone)

were: Order 215 sxs, 60/40pos 6%gel 1/2# floccel per sx.

Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by Herb Deines (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None xxxxxxxx

Operations Completed: Hour: 10:00AM Day: 13 Month: April Year: 1991

ACTUAL PLUGGING REPORT 1st plug at 3870' with 25 sxs. Arbuckle 3878'

2nd plug at 1525' with 25 sxs. Anhyrite 1510-1563'

3rd plug at 750' with 100 sxs. Dakota 449-749'

4th plug at 310' with 40 sxs. Surface pipe to 258'

5th plug at 40' with 10 sxs.

rathole with 15 sxs.

APR 22 1991

04-22-91

INVOICED

Remarks Allied Cementing (if additional description is necessary, use BACK of this form.)

DATE 4-29-91 observe this plugging.

INV. NO. 31698

4-13

Handwritten initials

Signed Herb Deines (TECHNICIAN)