

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22477-00-00
Spot: NWNWNWNW Sec/Twnshp/Rge: 20-13S-19W
4980 feet from S Section Line, 4980 feet from E Section Line
Lease/Unit Name: BEMIS Well Number: 1-20
County: ELLIS Total Vertical Depth: 3840 feet

Operator License No.: 101
Op Name: KCC FEE FUND
Address: 130 S. MARKET, ROOM 2078
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 342
Production: Size 4.5 feet: 3539
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/04/2002 9:00 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: ED POE Company: POE SERVICING INC Phone: (785) 475-3422

Proposed Plugging Method: According to KCC Rules & Regulations.
Ordered 275 sxs cement and 500# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/04/2002 3:15 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

8 5/8" S.P. at 342' w/225 sxs cement. 4 1/2" casing at 3539' w/175 sxs cement.
Perforated at 550' and 1200'.
Tubing to 1200' - pumped 100 sxs cement.
Pulled tubing to 600' and circulated with 40 sxs cement.
Pulled all tubing and squeezed 4 1/2" casing with 110 sxs cement and 500# hulls.
Max. P.S.I. 100#. S.I.P. 100#.
Tied to 8 5/8" x 4 1/2" annulus and pressured up to 1000#. Took no cement.
Total of 250 sxs 60/40 pozmix - 10% gel and 500# hulls.

RECEIVED

JUN 21 2002

KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. HOXIE TANK - WATER.

Plugged through: TBG

District: 04

Signed

Roger L. Moses
(TECHNICIAN)

