

4- 062599

3 19

144
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-051-21,480-00-00

NE SW SE /4 SEC. 22, 13 S, 19 W
990 feet from S section line
1650 feet from E section line

Operator license# 5331

Lease Rupp well # 1

Operator: Braden-Deem, Inc.

County Ellis

Address: 8100 E. 22nd N. #1800
Wichita, Kansas 67226
316-685-6464

Well total depth 3780 feet ^{122.85}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 233 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing Pulling, Inc. License# 6050

Address: Box 347, Chase, Kansas 67524

Company to plug at: Hour: 1:00P.M. Day: 19 Month: March Year: 92

Plugging proposal received from: Mike Kelso - Larry Wallert

Company: Braden-Deem, Inc. Phone: 913-483-2532

Were: Order 300 sks. of 60/40 posmix - 8% gel. - 5 sks. hulls.

Plugging Proposal Received by: Gilbert G. Scheck

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 5:00P.M., Day: 19, Month: March, Year: 92

Actual plugging report: 8 5/8" @ 233' w/140 sks. 4 1/2" @ 3773' w/250
sk. Top perf. @ 3581'. Plugged bottom with sand and 50 sks. cement to
3500'. Shot pipe 6 times and recovered 620'. Pump in 4 1/2" casing
and circulated cement from 1300' to surface. Hooked on to 8 5/8" and
squeezed to 500 P.S.I. Pulled all casing and used 300 sks. cement.
Max. pressure on 8 5/8" - 700 P.S.I. Shut in @ 500 P.S.I.
Max. pressure on backside - 500 P.S.I. Shut in @ 200 P.S.I.
Total sacks 300 cement.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy. plug: YES 1450 NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 2094 GL

If aid[] / did not[] observe the plugging.

Gilbert G. Scheck

DATE 4-7-92

INV. NO. 34874

(agent)

STATE CORPORATION COMMISSION
FILED
03-30-92