

4 060020

10-17

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-051,24,613-00-00

E2 SW SW, SEC. 6, T13 S, R 19 W4E

TECHNICIAN'S PLUGGING REPORT

660 feet from S section line

4290 feet from E section line

Operator License # 5238

Lease Name Amrein Well # 2

Operator: Petroleum Inc.

County Ellis 127.73

Name & Address Epic Center Suite 900

Well Total Depth 3930 feet

Wichita, KS 67202-1508

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 246

Abandoned Oil Well Gas Well Input Well SWD Well D&A xxx

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling Co. License Number 5422

Address Wichita, KS

Company to plug at: Hour: 1:30PM Day: 17 Month: October Year: 19 89

Plugging proposal received from Harold Maley

(company name) Abercrombie Drlg. Co. (phone) 316-262-1841

were: Order 205 sxs, 60/40 pos 6% gel 1/4# floccel per sx of cement.

Space all plugs with heavy drilling mud and through drill pipe.

OCT 30 1989  
10-30-1989  
CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by Herb Deines

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None XXXXXXXX

Operations Completed: Hour: 1:30PM Day: 17 Month: October Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 3900' w/20 sks Est. at 3900'

2nd plug at 1540' w/20 sks Anhydrite 1514-1557'

3rd plug at 770' w/100 sks Dakota 468-768'

4th plug at 300' w/40 sks Surface pipe to 246'

5th plug at 40' w/10 sks 40' plug w/wiper at 40'.

rathole with 15 sxs.

Remarks: Cemented by B. J. Tiran  
(If additional description is necessary, use BACK of this form.)

INVOICED  
do not serve this plugging.

DATE 11-2-89

Jeb S.

Signed Herb Deines (TECHNICIAN)

INV. NO. 26313