

6 060525

API NUMBER 15-051-23451-00-00

NE, SEC. 12, T 13 S, R 20 W

4950 feet from S section line

2310 feet from E section line

Lease Name Armbruster Well # 1

County Ellis 121.23

Well Total Depth 3730 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 208

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 6148

Operator: Walters & Walters

Name & Address 5924 Royal

Dallas, Texas

75230

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Five Star Well Ser. Inc. License Number 7088

Address Box 953, Hays, Mo. 67601

Company to plug at: Hour: 10:00AM Day: 2 Month: April Year: 19 85

Plugging proposal received from Dennis Muegel

(company name) Walters & Walters (phone) _____

were: Order 165 sh. 50% posmix - 6% Gel - 3% Cal. Cl., 5 sh. hulls, 20 sh. ball
& 8 5/8" plug.

Plugging Proposal Received by Arthur G. Schul
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30AM Day: 2 Month: April Year: 19 85

ACTUAL PLUGGING REPORT 8 5/8" - 208' w/ 125 sh. 5 1/2" - 3790' w/ 150 sh.

Top perf. at 3598'. Plugged bottom w/ 30 sh. cement to 3550'.

Shot pipe 2 times & recovered 2400'. Pumped in 8 5/8" - 4 sh. hulls, 25
sh. cement, 15 sh. Gel, 70 sh. cement, 5 sh. Gel, 1 sh. hulls, released plug &
followed w/ 70 sh. cement w/ 800 pounds pressure

RECEIVED STATE CORPORATION COMMISSION

APR 05 1985

04-05-1985

CONSERVATION DIVISION

(Wichita, Kansas)

Remarks: By ~~Arthur G. Schul~~ Arthur G. Schul

(If additional description is necessary, use BACK of (Wichita, Kansas))

I (did / did not) observe this plugging.

4-15-85

7725

MAY 09 1985 JUN 12 1985

Signed Arthur G. Schul
(TECHNICIAN)

4-28-85
28

AUX 2 3 1985 SF

FORM CP-2/3 Rev. 01-84