

4 060203

6-9

260
R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 051-24,742 -00-00

NW SE NW, SEC. 12, T 13 S, R 20 W/E

3630 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3655

Lease Name Warren Kraus Well # 1

Operator: Staab Energy & Leasing

County Ellis 122.75

Name & Address 2514 Haney Drive

Well Total Depth 3777 feet

Hays, KS 67601

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 212

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XXXXX

Other well as hereinafter indicated _____

Plugging Contractor Helberg Oil Co. License Number 5669

Address Morland, KS

Company to plug at: Hour: 2:00AM Day: 9 Month: June Year: 19 91

Plugging proposal received from Norman Staab

(company name) Staab Energy & Leasing (phone) _____

Order 190 sxs. 60/40pos 6%gel 1/4# floccel per sx.

Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by Herb Deines (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XXXXX

Operations Completed: Hour: 2:00AM Day: 9 Month: June Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 1430' with 25 sxs. Anhydrite 1416-1464'

2nd plug at 660' with 100 sxs. Dakota 360-660'

3rd plug at 265' with 40 sxs. Surface pipe to 212'

4th plug at 40' with 10 sxs.

rathole with 15 sxs.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Allied Cementing (If additional description is necessary, use BACK of this form.) Wichita, Kansas

JUL 03 1991
06-03-1991
CONSERVATION DIVISION
WICHITA, KANSAS

INVOICED

observe this plugging.

DATE JUL 19 1991

INV. NO. 32304

J.H.S.

Signed Herb Deines (TECHNICIAN)

Herb Deines