

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-051-23-325-00-00

NE, Sec. 13, T 13 S, R 20 W

330 feet from N/E section line

2310 feet from N/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050

Lease Name WARREN Well # 1

Operator: HUMMON CORPORATION

County ELLIS

Name & Address: 400 ONE MAIN PLACE  
WICHITA, KS.  
67202

Well Total Depth 3790 feet 123.18

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8" feet 206'

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor BLUE GOOSE DRILG. CO. License Number #5

Address BOX 1413 GREAT BEND, MS. 67530

Company to plug at: Hour: 12:30 AM Day: 8th Month: FEB. Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO LEROY BARRON

(company name) BLUE GOOSE DRILG. (phone) 316-792-5633

were: 8 5/8" - 206' EL SS. CUL #180' COMMON-2% GEL-3% CA-CL. (SUN ENT)

ORDER 160 50/50 Formix 4% GEL-3% CA-CL. AND 8 5/8" PLUG

SPOT WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS

1st PLUG @ 1440' EL #20' ENT. -> 2nd PLUG @ 600' EL #80' ENT.

3rd PLUG @ 240' EL #40' ENT. -> 4th PLUG HULLS-PLUG @ 40' ENT. 10' IN ENT NOLE (CIRCULATE)

Signed Marion Schmidt (TECHNICIAN) DOIC

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 6:00 AM Day: 8th Month: FEB. Year: 1983

ACTUAL PLUGGING REPORT

DID NOT PENETRATE ARBUCKLE.

PLUGGED AS STATED ABOVE - BY SUN ENT.

RECEIVED STATE CORPORATION COMMISSION

MAR 14 1983

CONSERVATION DIVISION Wichita, Kansas

Remarks:

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED

MAR 28 1983

DATE

NV NO.

3767-W

Signed Marion Schmidt (TECHNICIAN) (DOIC)

FORM CP-2/3 Rev. 9-82