

Plugged

4-041680

4-27

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 S. MARKET, ROOM #2078
WICHITA, KANSAS 67202

API number: 15-051-22,321-00-00
SE
NE-NE SW /4 SEC. 22, 13 S, 18 W
2310 990 feet from S section line
2970 2970 feet from E section line

Operator license# 3613 Lease Braun well # B-1
Operator: Hallwood Petroleum, Inc. County Ellis 120.02
Address: P.O. Box 378111 Well total depth 3693 feet
Denver, Colorado 80237 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 146 feet

Aband. oil well X, Gas well , Input well , SWD , D & A
Plugging contractor: Halliburton Services License#

Address:
Company to plug at: Hour: A.M. Day: 27 Month: April Year: 95

Plugging proposal received from: Aven Weaverling
Company: Phone:

Were: 5 1/2" casing set at 3691' w/180 sxs. cement. Perf. at 3256' -
3646'. D.V. at 1334' cwc. with 310 sxs. cement.

Plugging Proposal Received by: Dennis Hamel
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: P.M., Day: 27, Month: April, Year: 95

Actual plugging report: Pumped 25 sxs. cement and 200# hulls, followed with
10 sxs. of gel, followed with 150 sxs. cement with 200# hulls. Max. P.S.I.
1900#. S.I.P. 500#. Dug out head - cut off pipe - found cement down 400'
in 5 1/2" and down 59' in 8 5/8". Dumped 3 yards of ready mix to fill
casing.

Remarks:
Condition of casing(in hole): GOOD X BAD Any plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did[X] / did not[] observe the plugging. Dennis Hamel
(agent)

RECEIVED
JUN 09 1995
CONSERVATION COMMISSION

INVOICED

DATE JUN 09 1995
INV. NO. 42923

API#15-051-22321-00-00

DresserAtlas

DRESSER

Cemotop

FILE NO.	COMPANY <u>ENERGY RESERVES GROUP</u>	
	WELL <u>N. BRAUN</u>	
	FIELD <u>MARVIN EXT.</u>	
	COUNTY <u>ELLIS</u>	STATE <u>KANSAS</u>
LOCATION: <u>NE-SE-SW</u>		Other Services GR-N
SEC <u>22</u> TWP <u>13S</u> RGE <u>18W</u>		

Permanent Datum <u>GROUND LEVEL</u>	Elev. <u>2057</u>	KB <u>2062</u>
Log Measured from <u>KELLY BUSHING</u>	<u>5</u> Ft. Above Permanent Datum	DF <u>-</u>
Drilling Measured from <u>KELLY BUSHING</u>		GL <u>2057</u>

Date	3-13-81	
Run No.	-	
Type Log	CEMETOP	
Depth-Driller	3700	
Depth-Logger	3648	
Bottom Logged Interval	3646	
Top Logged Interval	0	
Type Fluid in Hole	WATER	STAT. G.
Salinity Ppm Cl.	-	
Density Lb./Gal.	-	JUN 2 1991
Level	FULL	
Max. Rec. Temp. Deg. F	-	
Opr. Rig Time	2 HRS.	
Recorded By	BERTSCH	
Witnessed By	MR. HUTTON	

Run No.	Bore Hole Record			Casing Record			
	Bit	From	To	Size	Wgt.	From	To
				5-1 1/2		SURF	3691

APR 2 1995