

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-051-23,213-0000

NE, Sec. 22, T 13 S, R 18 W/E

990 feet from N/S section line

330 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5252

Lease Name M Braun Well # 4

Operator: Jay-Lan Corporation
Name &
Address 207 W. 12th, Hays, Ks. 67601

County Ellis

Well Total Depth 3741 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 200'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Jay-Lan Corporation License Number 36

Address 207 W. 12th, Hays, Ks. 67601

Company to plug at: Hour: 6:30PM Day: 13 Month: 11 Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO R. P. Nixon

(company name) Jay-Lan Corporation (phone) 913-628-3834

were: Order 180 sacks 50% permix - 4% bel. - 3% cal. U. + 8 5/8" plug. Spot w/ drill stem w/ heavy mud between all plugs. 1st plug C 3740' w/ 20 sacks, 2nd plug C 1397' w/ 20 sacks, 3rd plug C 750' w/ 80 sacks, 4th plug C 250' w/ 40 sacks, 5th plug C 40' w/ 10 sacks

Signed [Signature]
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6:30PM Day: 13 Month: 11 Year: 1982

ACTUAL PLUGGING REPORT 8 5/8" - 200' S.P. case w/ 135 sacks - common - 2% bel. - 3% cal. U.

Ordered 180 sacks 50% permix - 4% bel. - 3% cal. U. + 8 5/8" plug. Spot w/ drill stem w/ heavy mud between all plugs. 1st plug C 3740' w/ 20 sacks, 2nd plug C 1397' w/ 20 sacks, 3rd plug C 750' w/ 80 sacks, 4th plug C 250' w/ 40 sacks, 5th plug - solid bridge of bulls + plug C 40' w/ 10 sacks. Circulated 10 sacks in rat hole.

Remarks: Drilled into Arbruchle

RECEIVED
STATE CORPORATION COMMISSION
NOV 22 1982
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (~~did~~ / did not) observe this plugging.

12-23-82
1912-W

Signed [Signature]
(TECHNICIAN)