

To:
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-205-19934-00-00
NW SE NW Sec/Twp/Rge Sec 21 T30S R17E
3307 (gps) feet from south section line
3904 (gps) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101
Operator: State Of Kansas Fee Fund
Name & Katzer Lease Project
Address _____
AB oil well XXXXXX Gas Well _____

Lease/Well# Katzer KAT01
County Wilson
Well Total Depth 2310 (est) feet
Production Pipe: NA Size Feet NA
Surface Casing: 6.25 Size Feet NA
SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: K-W Oil Well Service, Inc Lic. # 3097

Address: 19450 Ford Road, Chanute, Kansas 66720

Company to plug at: Hour: _____ Day: 12 Month: 8 2010

Plugging proposal received from: Robert Kepley

Company Name: K-W Oil Well Service, Inc Phone: 620-433-7730

Were: Wash well to TD and fill from btm to top with portland cement thru one inch cement string.

Plugging Proposal Received by: Alan M. Dunning

TECHNICIAN

Plugging attended by Agent: All _____ Part _____ None XXXXXX

Operations Completed: Hour: _____ Day: 12 Month: 8 2010

Actual Plugging Report: The drill rig was moved to location and the well drilled to 150' thru wood

and soft cement. The rig drilled on iron from 150' to 300'. The drill string was removed and a 1" cement
string lowered to 300'. The well was pumped full of cement from btm to top thru this cement string. A total
of 51 sacks of portland cement were used to plug well. The well was cut off below plow depth and the
location restored.

Remarks: Control # 20100098-001

(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

Signed:
RECEIVED

JAN 26 2011

KCC WICHITA

Alan M. Dunning
TECHNICIAN