

4-060302

3-10

128
R

15-051-03503-0000

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: ~~15-12-29-48~~

82 82 NW /4 SEC. 21, 11 S, 17 W
2970 feet from S section line
3960 feet from E section line

Operator license# 5363 Lease Hadley well # 6

Operator: Berexco, Inc. County Ellis

Address: Box 723 Well total depth 3373 feet ^{109.62}
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 1080 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Co Tools License# -

Address: _____

Company to plug at: Hour: 12:00P.M Day: 10 Month: March Year: 92

Plugging proposal received from: Bob Grant

Company: Berexco, Inc. Phone: 913-628-6101

Were: Order 425 sxs. 65/35 posmix - 8% gel and hulls.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 2:00P.M., Day: 10, Month: March, Year: 1992

Actual plugging report: 8 5/8" to 1080'. 5 1/2" to 3368'. Shot one time and pulled 2000' casing. Tied onto surface pipe and pumped 25 sxs. cement followed by 350 sxs. cement with 500# hulls. Max. 750#. S.I.P. 500#.

MAR 26 1992
03-26-92

Remarks: B.J. Services Cementing. Dakota Plugged.

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO

Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO

Plugged through TUBING , CASING . Elevation: N/A GL

I did[] / did not[] observe the plugging. Herb Deines

DATE 3-27-92

INV. NO. 34853

Herb S.

(agent)

INVOICED