

4 060163

2-18

207

051-05798-0000

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-~~8-4-40~~

SE SE NW, SEC. 21, T 11 S, R 17 W/X

2970 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

Lease Name Hadley Well # 3

Operator: BEREXCO Inc.

County Ellis 110.89

Name & Address East 8th St.

Well Total Depth 3412 feet

Hays, KS 67601

Conductor Pipe: Size _____ feet

Surface Casing: Size 13" feet 101

Abandoned Oil Well XXXXXX Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Co Tools License Number _____

Address _____

Company to plug at: Hour: 9:00AM Day: 18 Month: February Year: 19 91

Plugging proposal received from Ted Crawford

(company name) BEREXCO Inc. (phone) _____

were: Order 200 sxs. Common cement and 200 sxs. 60/40pos 8%gel

Perf. Anhydrite and base of Dakota at 1150' and 535' respectively

Fish in hole at 1450'. Milled on and couldn't get through.

Emergency permission granted by district office to plug well.

Plugging Proposal Received by Don Butcher
(TECHNICIAN)

Plugging Operations attended by Agent?: All XXXXXXXX Part _____ None _____

Operations Completed: Hour: 11:59AM Day: 18 Month: February Year: 19 91

ACTUAL PLUGGING REPORT 13" to 101', 7" to 3364' Liner 3346'-3377'. Perf at 1150' and 535'.

Run tubing to TD at 1450 and pmp 200 sxs. common cement. Pulled 1000' of tubing and pmp.

35 sxs. 60/40pos 8%gel to circ cement to surface. Pulled tubing and tied onto annulus.

Pmp 15 sxs. cement. Max 270# SIP 210#. Tied onto casing and pmp. 135 sxs. 60/40pos 8%gel

Max 500# SIP 350#.

STATE OF

Remarks: B-J Services Cementing
(additional description is necessary, use BACK of this form.)

FEB 21 1991
02-21-91

INVOICED

I (did XXXXXX observe this plugging.

DATE 2-25-91

INV. NO. 30879

Herb S.

Signed [Signature]
(TECHNICIAN)

Herb Deines