

6 041084

10-11 051-1931de-0000
API NUMBER 15- 2-2-52 3007

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

240' W S/2 NW SEC. 23, T 11 S, R 17 W/E

3300 feet from S section line
4200 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6484

Lease Name Rumsey Well # W-2 SWD

Operator: Anderson Energy Inc.

County Ellis 126.10

Name & Address 200 East First Street

Well Total Depth 3880 feet

Suite 414

Conductor Pipe: Size _____ feet

Wichita, Ks. 67202

Surface Casing: Size 10 3/4 feet 1077' w/500 sks

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing/Express Well Service License Number _____

Address Russell, Ks. Victoria, Ks.

Company to plug at: Hour: 8:00 AM Day: 11 Month: Oct Year: 19 89

Plugging proposal received from Steve Robben

(company name) Express Well Service (phone) _____

were: 7" casing set at 3470' w/200 sks: OH 3470 - 3880'

5 1/2" cement lined tubing and packer to 3450' left in hole: Cleaned 5 1/2" casing to 1850'.

Perforated casing at 1850'. Ordered 100 sks common plus 500 sks 65/35 poz 8% gel w/1/4# f.c. plus 5 sks hulls.

RECEIVED
STATE CORPORATION COMMISSION

NOV 14 1989
11-14-89

Plugging Proposal Received by Dennis Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30PM Day: 11 Month: Oct Year: 19 89

ACTUAL PLUGGING REPORT Ran tubing to 1800'; pumped 100 sks common w/1/4# f.c. pulled 500'

of tubing; umped 150 sks 65/35 poz 8% gel w/1/4# f.c. to curc; pulled tubing, tied onto

5 1/2" casing pumped add. 200 sks cement: cement circ annulus of 7" - 10 3/4" casing: shut in

same pumped in add 50 sks cement: 300# s.i. 700# Max. Hooked up 5 1/2" - 7" pressed up to 800#.

Remarks: Would not circ: shut in:
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Dennis Hamel (TECHNICIAN)
Dennis Hamel

DATE 11-15-89
INV. NO. 26455