

4-19
4-071039

15-051-30655-00-01

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 10-43

W2 NW NE /4 SEC. 06, 13 S, 20 W
4620 feet from S section line
2310 feet from E section line

Operator license# 5364Lease Bittle B well # 3Operator: Beren CorporationCounty EllisAddress: Box 723Well total depth 4041 feetHays, Kansas 67601Conductor Pipe: 0 inch @ 0 feetTed CrawfordSurface pipe 7 Inch @ 3830 feetAband. oil well , Gas well , Input well , SWD X, D & A Plugging contractor: Allied Cementing - Co Tools License# -Address: Russell, Kansas 67665 - Hays, Kansas 67601Company to plug at: Hour: A.M. Day: 19 Month: April Year: 93Plugging proposal received from: George JorgensenCompany: Beren CorporationPhone: 913-628-6101

Were: 10 3/4" - 197' S.P. cwc. w/90 sx. cement. 7" casing @ 3830'
w/125 sx. cement. 4 1/2" casing @ 3924' w/350 sx. cement. Casing
squeezing's - 1900' w/200 sx. - 780' to 1310' w/250 sx. cement.

Proposal 300 sx. 60/40 pozmix - 10% gel. - 1/4# flocele per sx.
100 sx. common cement. Spot and displace all cement through tubing.
Load 4 1/2" casing and squeeze all annulus with cement. Shut in under
pressure.

Plugging Proposal Received by: Marion J. SchmidtPlugging operations attended by agent? All[X], Part[], None[]Completed: Hour: 1:45 P.M., Day: 19, Month: April, Year: 93

Actual plugging report: Beren ordered 100 sx. Common Class A and 300 sx
60/40 pozmix - 10% gel and 1/4# flocele per sack. Spotted and displaced
all cement through tubing. 1) Perforate casing at 1550' - 780' - 107'.
2) 2 3/8" tubing at 3800' w/100 sx. cement Class A Common. 3) 2 3/8"
tubing at 1600' w/90 sx. cement. Cement circulated out of 4 1/2" casing.
4) Squeezed 10 3/4" x 7" annulus with 100 sx. cement - 100 P.S.I.
5) Squeezed 4 1/2" casing with 10 sx. cement - 400 P.S.I. 6) 4 1/2" x 7"
annulus cement at surface.

Remarks: Allied Cementing - Russell, KansasCondition of casing(in hole): GOOD BAD X Anhy. plug: YES X NO Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO Plugged through TUBING X, CASING . Elevation: I did [X] / did not [] observe the plugging.DATE 5-14-93INV. NO. 37689

Form CP-2/3