

6 010355

15-051-30176-0000

API NUMBER 15-

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SW-SW-NW, SEC. 6, T. 13 S, R. 20 W

TECHNICIAN'S PLUGGING REPORT

Operator License # 5146  
Operator: Rains & Williamson  
Name & Address: 220 W. Douglas  
Wichita KS.

\_\_\_\_\_ feet from S section line  
\_\_\_\_\_ feet from E section line  
Lease Name Bittel Well # 1  
County Ellis 124.71  
Well Total Depth 3837 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 225

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rains & Williamson License Number 5146  
Address same.

Company to plug at: Hour: 10 AM Day: 29 Month: 5 Year: 19 85

Plugging proposal received from Gerald Ptatchek.

(company name) Rains & Williamson (phone) \_\_\_\_\_

were: order 300 sx cem. 50/50 permix 670 gal 390 c.c. -  
4 sx. Hulls. - 28 sx gel. - 1. 5 1/2 plug. -  
Squeezed @ 770 w/ 200 sx  
5 1/2 @ 3834

FLOU-2174 Anhyd. 1505  
Dakota 1700 Plugging Proposal Received by Dale F. Butthorpe  
474 (TECHNICIAN)

Plugging Operations attended by Agent?:  All \_\_\_\_\_ Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:20 AM Day: 29 Month: 5 Year: 19 85

ACTUAL PLUGGING REPORT pumped down csg. 50 sx cem. -  
28 sx. Gel w/ 3 sx hulls. Released plug  
pumped 100 sx cem. w/ 1 sx. hulls. 0-pres.  
pumped down 8 5/8 5 sx. cem. 500# press.  
pumped down 5 1/2. 145 sx cem. 150# pres.

Remarks: Halliburton 6-7-85  
(If additional description is necessary, use BACK of this form.)

**NOTICED** If you do not receive this plugging.

DATE 6-12-85

INV. NO. 8472 5-29

Signed Dale F. Butthorpe 24  
(TECHNICIAN) 6-6-85