

6 070453

R 301-113

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- OSI-30318-00-00
S2 S2 NW
SEC. 6, T. 12 S., R. 20 W.
2970 feet from S section line
3760 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5146

Lease Name E. Bittel Well # 4

Operator: Rains + Williamson Oil
Name & Address: 425 Page Court, 220 Douglas
Wichita, Kansas
Wilton Rains, Pres.

County Ellis 124.31
Well Total Depth 2825 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated 0

Plugging Contractor B.V. Titan License Number

Address South Canterbury Rd Hays, Kans. 67601

Company to plug at: Hour: 12:00 PM Day: 20th Month: Feb Year: 19 86

Plugging proposal received from Eerald Ptasczek

(company name) Rains + Williamson (phone) 913-726-3252

were: 8 5/8" - 225 FT SP CUG #/165 SK cmt, 5 1/2" csg set @ 2818' #/100 FT

5 1/2" csg squeezed @ 780 # #/200 SK cmt, open hole 7'

Perfs: 2836 FT, Ebr. 2171 - Ann. 1499, Leak In Dakota

Perf. in Anhydrite @ 1510' (2 holes) Order Proposal 280 SK 60/40 Formix 6% Gel 3% CaCl 20 SK Gel

20 SK Gel, 5 SK Gels, 5 1/2" Plug. Load Both Annulus and 5 1/2" csg w/ cement and Pressure

Plugging Proposal Received by Marion Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:45 PM Day: 20th Month: Feb Year: 19 86

ACTUAL PLUGGING REPORT Ordered 280 SK 60/40 Formix 6% Gel 3% CaCl 20 SK Gel, 5 SK Gels, and 5 1/2" Plug.

Pumped in 5 1/2" csg #/50 SK #/2 SK mixed in, - 15 SK Gel #/2 SK Gels, 30 SK Cmt, (1300 P.S.I.g), 5 SK GEL. 1300 P.S.I.g, 1/2 SK Gels, Released Plug and 100 SK cmt. 500 P.S.I.g - shut in @ 400 P.S.I.g.

Pumped 100 SK cmt @ In Annulus, 150 lbs P.S.I.g

Remarks: Cemented By B.V. Titan.

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

STATE CORPORATION COMMISSION
Signed Marion Schmidt (TECHNICIAN)
DOIC.

FEB 28 1986

FEB 20 1986
2-28-86
CONSERVATION DIVISION
Wichita, Kansas

INV. NO. 12788

FORM CP-2/3
Rev. 01-84

7
2-28-86