

6 041061

8- / 1503720066-00-00

API NUMBER 15-

5-29-67

To: STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING SECTION NE NW SE, SEC. 6, T 13 S, R 20 W 4E
 200 COLORADO DERBY BUILDING
 WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 9346

Operator: Glenn Diehl Oil Oper
Name &

Address Box 234

Hays, Ks. 67601

Lease Name Bittel A Well # 3

County Ellis 124.61

Well Total Depth 3834 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 236' w/150 sks

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated

Halliburton Cement

Plugging Contractor License Number

Address Hays, Ks.

Company to plug at: Hour: 8:30AM Day: 1 Month: August Year: 19 89

Plugging proposal received from Glenn Diehl

(company name) Same (phone)

were: 5 1/2" casing set at 3819' w/125 sk. Open hole at 3819' 34'. D.V. at

1507' circ w/350 sks cement. Ordered 325 sks 65/35 poz 10% gel w/1/4# f.c. plus 5 sks

hulls.

Plugging Proposal Received by Dennis L. Hamel

(TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 11:30AM Day: 1 Month: August Year: 19 89

ACTUAL PLUGGING REPORT Pumped in 5 1/2" casing 250 sks cement w/1/4# f.c.

plus 5 sks hulls mixed in cement. Max 300#. S.I. 300# psi. Pumped in 8 5/8" casing

0 sks cement. Max 500#. S.I. 500# psi.

RECEIVED
 STATE CORPORATION COMMISSION

AUG 28 1989

8-28-89

CONSERVATION DIVISION
Wichita, Kansas

Remarks:

(If additional description is necessary, use BACK of this form.)

I did observe this plugging.

Signed Dennis L. Hamel

(TECHNICIAN)

Dennis L. Hamel

DATE 8-30-89

INV. NO. 25753

FORM CP-2/3
 Rev. 01-84