

4-16

75
R

4-071036

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-051-21,777-00-00

NE /4 SEC. 06, 13 S, 20 W
4950 feet from S section line
1810 feet from E section line

Operator license# 5364 Lease Bittel B well # 7

Operator: Beren Corporation County Ellis

Address: Box 723 Well total depth 3855 feet
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 243 feet
w/150 sx.

125.28

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License#

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 16 Month: April Year: 93

Plugging proposal received from: George Jorgensen

Company: Beren Corporation Phone: 913-628-6101

Were: 5 1/2" casing set @ 3841' w/150 sx. cement. O.H. @ 3841'.
Anhy. - Perf. @ 1550'. Dakota @ 775'. W.L.M. 1025'.
Ordered 275 sxs. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 300# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 8:30P.M., Day: 16, Month: April, Year: 93

Actual plugging report: Spot bottom plug 100 sx. @ 2303'.
Spot 2nd. plug 225 sx. w/100# hulls @ 1303' circulated and squeeze
at surface. Max. P.S.I. 400 #. S.I. 200 #.
8 5/8" S.P. - Squeeze 75 sx. cement w/100# hulls. Max. 300#.

Remarks: Top of fluid 220'.
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES NO
Plugged through TUBING X, CASING . Elevation:

I did X did not observe the plugging.

INVOICED
DATE 5-3-93
CPL. NO. 37641

RECEIVED
APR 30 1993
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
(agent) Wichita, Kansas
Form CP-233as