

4-041462

4-13

15-051-30258-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 4-66

SE NW NW /4 SEC. 06, 13 S, 20 W
4290 feet from S section line
4290 feet from E section line

Operator license# 5364 Lease Bittel well # B-5

Operator: Beren Corporation County Ellis

Address: Box 723 Well total depth 3870 feet ^{125.77}
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 265 feet
w/200 sx.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License#

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 11 Month: April Year: 93

Plugging proposal received from: George Jorgensen

Company: Beren Corporation Phone: 913-628-6101

Were: 5 1/2" casing set @ 3869' w/100 sx. cement. Anhy.-Perf. @ 1550'
Dakota @ 750'. W.L.M. 3855'. Squeezed @ 1560' - 1200' w/200 sx.
Squeezed @ 780' -950' w/200 sxs.
Ordered 275 sxs. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 300# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 2:00P.M., Day: 13, Month: April, Year: 93

Actual plugging report: Bottom plug - 25 sxs. w/100# hulls @ 3850'.
2nd. plug - 25 sxs. @ 2250'. 3rd. plug - 175 sxs. cement w/100# hulls
@ 1550'. Circulate and squeezed at surface. 8 5/8" S.P. Squeezed
50 sxs. cement w/100# hulls. Max. 800#. S.I. 800#. Max. 300#.
S.I. 300#.

Remarks:
Condition of casing(in hole): GOOD BAD X Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation: GL

I did X / did not observe the plugging.

Dennis J. Hamel

(agent)

Form CP-2/3

RECEIVED
STATE CORPORATION COMM
6-9-93
JUN 9 1993
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 6-11-93

INV. NO. 378.78