


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Mandatory Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15051-01657-0000
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Ellis County, Sec. 12 Twp. 13 Rge. 18 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NW NW NE
Lease Owner Lawrence Supply
Lease Name Ubert Well No. 1
Office Address Farmers & Merchants State Bank, Claflin, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed _____ 19 38
Application for plugging filed October 27 19 58
Application for plugging approved October 30 19 58
Plugging commenced October 31 19 58
Plugging completed October 31 19 58
Reason for abandonment of well or producing formation Non-commercial

If a producing well is abandoned, date of last production August 19 58
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Arbuckle Depth to top 3597 Bottom 3624 Total Depth of Well 3624 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle	Wtr. show oil	3597	3624	12 1/2"	280	None
Other formation tested				7"	3599	None
Lansing K C	Perf. Wtr.	3342	3344	5 1/2" liner	from surface	to 1000'
	Perf. Wtr.	3367	3369			None
	Perf. Wtr.	3388	3390			
	Perf. Wtr.	3422	3424			
	Perf. Wtr.	3433	3435			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3624 feet to 3560 feet for each plug set.

Set rock and cement bridge at 3250 using 15 gal. rock and 5 sacks cement. Filled from 3250 to 550 with mud. Set bridge plug using 10 gal. rock and wiper plug. Pumped hole full of cement from 550 to surface by Halliburton.

12 1/2" pipe circ. with cement.
7" squeezed with cement to surface
5 1/2" liner circ. with cement to surface.

RECEIVED
STATE CORPORATION COMMISSION
JAN 10 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Tompkins Drilling
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Drego, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Maxine Muller
Wafferness Ave.
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of January, 19 59

My commission expires 10-15-60

Notary Public.

PLUGGING
FILE SEC 12 T 13 R 18W
BOOK PAGE 149 LINE 45

Lawrence Supply Co.
#1 Ubert
NW NW NE
Section 12-13S-18W
Ellis County, Kansas
Elevation: 2072

15-051-0657-00-00

The above well was drilled by Atlantic Refining Company in 1938.
It was originally completed for 400 BOPD in the Arbuckle.

Top Heebner	3294'	
Top Toronto	3316'	
3317'-3322'		Limestone white, fine crystalline, oolitic, fair porosity, good saturation.
Top Lansing	3341'	
3367-3377'		Limestone white, medium crystalline, poor porosity, trace spotted saturation.
3388-3398'		Limestone white, oolitic, fair porosity, fair saturation.
3422-3427'		Limestone white, oolitic and oolitic, fair saturation.
3432-3442'		Limestone as above.
Top Arbuckle	3597	
Note:		These samples were in very poor condition.
TD	3624	
		7" pipe at 3599.

RECEIVED
STATE GEOLOGICAL SURVEY
JAN 10 1959
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 12 T 13 R 18W
BOOK PAGE 149 LINE 45