


15051-19208-00-00
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas



Locate well correctly on above Section Plat

Ellis County. Sec. 12 Twp. 13 Rge. 18 (E) W (W)
Location as "NE/CNWxSWx" or footage from lines: C N/2 NE SE
Lease Owner: Leo J. Dreiling Oil Co.
Lease Name: Staab Well No. B # 1
Office Address: Victoria, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed: 9-16-19 60
Application for plugging filed: 6-18-19 65
Application for plugging approved: 6-18-19 65
Plugging commenced: 5-11-19 65
Plugging completed: 6-5-19 65
Reason for abandonment of well or producing formation: No productive

If a producing well is abandoned, date of last production: 4-30-19 65
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well: Mr. Petty-Hays, Kansas
Producing formation: Depth to top: Bottom: Total Depth of Well: Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
205	8-5/8" Surface Csg.					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pumped down 5 1/2" csg. 40 sacks gel., followed with plug and 70 sacks common cement. Did not pressure up. On vacuum when completed. Cement was down 1600', filled hole to 700' with heavy mud. Plug and cement to Surface. Completed 6-5-65.

RECEIVED
STATE CORPORATION COMMISSION

JUN 21 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor: L. J. Dreiling & Sons, Inc.
Address: Victoria, Kansas

STATE OF Kansas, COUNTY OF Ellis, ss.
I, Leo F. Dreiling, a partner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) Leo F. Dreiling Victoria, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 18 day of June, 19 65

My commission expires October 26, 1965
Elmer Wells
Notary Public.

D R I L L E R S L O G

#1 Stabb

CASING RECORD: 205.67' 3-5/8" surface casing	COMPANY: Leo J. Drilling Oil Co.	DESCRIPTION: C/Ne NE SE Section 12-13S-18W Ellis County, Kansas
TOTAL DEPTH: 3695'	CONTRACTOR: Strata Drilling, Inc.	ELEVATION: 2145' KB
	COMMENCED: September 7, 1960	
	COMPLETED: September 16, 1960	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay & Pest Rock	0	70	Ran 198.67' used 3-5/8" surface casing; set and cemented at 205.67' with 150 sacks of sunset cement. Plug down @ 6:05 A. M. 9-8-1960.
Shale	70	300	
Shale & Shells	300	860	
Sand	860	1015	
Red Bed	1015	1110	
Shale & Shells	1110	1415	
Shale	1415	1980	
Shale & Lime	1880	2290	
Lime	2290	2455	
Lime & Shale	2455	3175	
Lime	3175	3282	DST #1 3685'-3695' tool open 30 min. strong blow. Recovered 120' muddy oil, 365' clean oil, 55' gas in pipe. IFP 0 lbs. FFP 60 lbs. BHP 260 lbs. in 20 minutes.
Lime & Shale	3282	3295	
Lime	3295	3695	

Total Depth 3695'

Ran 3688' new 5 1/2" casing; set and cemented with 125 sacks of cement. Plug down @ 12:15 A. M. 9-16-1960.

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp
Charles W. Steincamp, President

Subscribed and sworn to before me this 16th day of September, 1960.

Elaine H. Taylor
Elaine H. Taylor, Notary Public

My Commission Expires:
December 14, 1961

RECEIVED
STATE CORPORATION COMMISSION

JUN 21 1961

CONSERVATION DIVISION
Wichita, Kansas